

Job Number: 19/0364
Record No.: CC-0002**CHANGE IN CONTRACT**

Harris County Flood Control District


Contractor:	L N MCKEAN INC	Date:	8/24/2021			
Address:	PO Box 130250	PO Number:	P0000000730			
	The Woodlands, TX	PS Fund:				
		PS Activity:				
Project Name:	Phase 4 Channel Conveyance Improvements					
Project ID:	C106-03-00-C007					
<i>Contractor: In connection with your contract dated 1/28/2020, for construction of the above mentioned job, the work or material outlined below was not comprehended in the original contract, or the following deduction is desired. When this order has been properly filled in, and approved, please proceed to do this work in accordance with the alterations set out below:</i>						
Description of Change Desired						
<p>The purpose of this change is to adjust pay item quantities for actual site conditions and to increase contract time for added scope and inclement weather.</p> <p>Stormsewer Outfall Revision The stormsewer outfall to be replaced at STA 37+15 was found to actually be a 36" RCP further upstream. Per RFI #14, the proposed outfall pipe size is to be increased to 36" RCP. Two (2) days are added to the contract for the added rework resulting from the change. (Planned 24" pipe had been partially installed when the 36" upstream pipe was discovered.)</p> <p>Inclement Weather Days This contract change adds time to the Contract in accordance with inclement weather provisions for weather days experienced from 3/31/20 to 7/31/21. The number of inclement weather days has exceeded 110% of the provided 67 weather days included in the contract. Total approved weather days from 3/31/20 to 7/31/21 = 96 days. (96 days approved) - (67 days included in contract) = 29 days to be added to the contract for inclement weather.</p> <p>This change results in a net increase of \$1,680.00 to the contract value and adds a total of 31 days to the contract for added scope and inclement weather.</p>						
Estimate of Cost						
Change Type	Pay Item ID	Pay Item Name	Unit	Quantity	Unit Price	Amount
Decrease	02611-02	24-INCH REINFORCED CONCRETE PIPE	LF	-16.00	150.00	-2,400.00
					Subtotal	-2,400.00
Increase						
					Subtotal	0.00
Addition	02611-04	36-INCH REINFORCED CONCRETE PIPE	LF	16.00	255.00	4,080.00
					Subtotal	4,080.00

County Auditor's Form 1258
Harris County TX (REV. 5/17/2017)

	Changes in Calendar days: 31	
--	------------------------------	--


If applicable, the Auditor's certification is made when the purchase order is amended in the system.

TOTAL ADDED TO CONTRACT:	4,080.00
TOTAL DEDUCTED FROM CONTRACT:	-2,400.00
NET CHANGE:	1,680.00

Approved: 
15515ECB376C454...


Print Name: Gene Rushing
Project Manager

Basis and Work Agreeable to Us.

Approved: 
2E985FDADEC4476...

Print Name: Alan Black
HCFCF, Executive Director

Contractor: L N MCKEAN INC

Signed: 
244F903922E344F...
For the Contractor

Print Name: Lee McKean III

Authorized in Minutes Of: _____

